BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Satellite Town Sub Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
BBMP, Bangalore

Approved Tender SCHEDULE –'B'

Name of Work:-Madified estimate work Construction of drains and concrete roads in Sanitary Core in ward no 04

Sl.No	Description of work	Unit	Approved Qty	Rate quoted by the contractor K Ravikumar	
				Rate	Rate in words
1	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum	203.28	264.00	Rupees two hundred sixty four only
			43.41	262.80	Rupees two hundred sixty two and paise eighty only
2	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS 4.1,4.2 (Item no: 4.3,Page no12, PWD SR 2014-15)	Cum	100.18	4800.00	Rupees four thousand eight only

5	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with super plasterise @ 3lts conforming etc as per specification&direction of the engineer incharge of work(pwd sr2014-15,p.no13,sno4.11)	Cum	38.65	6000.00	Rupees six thousand only
			23.41	6024.04	Rupees six thousand twenty fopur and paise four opnly
6	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr 2014-15,p.no17,s.no 4.46)	Qtl	52.75	7900.00	Rupees seven thousand nine hundred only
7	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses, buttresses plinth and string course including cost of all materials,labour complete asperspecification. Specification no.KBS 4.6.2 (pwd sr2014-15,p.no15/4.31)	Sqm	486.40	292.00	Rupeestwo hundred ninety two only
8	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	183.42	1230.00	Rupees one thousand two hundred thirty only
9	KSRB 4.2.7 : Providing and laying in position reinforced cement concrete of nominal mix 1:1:2 with 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for R.C.C.beams, columns of all sizes in foundation plinth and superstructure ground floor level for roof slabs, staircase, lintels, columns, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.(excluding cost of steel, fabrication & plastering) Specification No. KBS 4.1, 4.		49.36	5300.00	Rupees five thousand three humndred only

~~18~~ 8	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 130, PWD SR 2014-15)	Cum	203.28	68.00	Rupees sixty eight only
			43.41	67.58	Rupees seven and paise fifty eight only

Signature of the contractor

Executive Engineer
Yelahanka Division
BBMP, Bangalore

[illegible],01,991.00 (Rupees [illegible])